

Job Name	HYATT PLACE-OMAHA	Est. No.	GVS-214
Job Address	OMAHA, NEBRASKA 68102	Rev. No.	
Customer	SIOUX CITY FOUNDRY	Date	17-Nov-11

SUPPLEMENT REPORT Drawings Dated 10-26-2011 Addendums:

PLACING SEPARATIONS (BASE BID - CONCRETE BLACK REBAR INSTALLED:) BASE								
S#	Bid	Description	Pounds	Bar LF	Tons	Ave Size	Lbs/FT	Sep #
1	Concrete Pile	Concrete Pile	136,454.00				1.909	1
		Sum	136,454.00		68.23			
2	Pile Cap	Pile Cap	50,607.00				2.981	2
		Sum	50,607.00		25.30			
3	Mat Footing	Mat Footing	21,965.00				2.667	3
		Sum	21,965.00		10.98			
4	Wall Footing	Wall Footing	991.00				0.668	4
		Sum	991.00		0.50			
5	Grade Beam	Grade Beam	68,197.00				1.405	5
		Sum	68,197.00		34.10			
6	Slab On Grade	Slab On Grade	3,464.00				1.319	6
		Sum	3,464.00		1.73			
7	Level 6 Hotel PT Beam	Level 6 Hotel PT Beam	24,065.00				1.213	7
		Sum	24,065.00		12.03			
8	Level 6 Hotel PT Slab	Level 6 Hotel PT Slab	52,001.00				1.276	8
		Sum	52,001.00		26.00			
9	Concrete Wall	Concrete Wall	5,904.00				1.044	9
		Sum	5,904.00		2.95			
10	Shear Wall	Shear Wall	84,478.00				1.055	10
		Sum	84,478.00		42.24			
11	Concrete Column	Concrete Column	72,435.00				1.396	11
		Sum	72,435.00		36.22			
12	Cmu Wall	Cmu Wall	7,308.00				1.043	12
		Sum	7,308.00		3.65			
13	Generator Pad	Generator Pad	557.00				0.879	13
		Sum	557.00		0.28			
13	Transformer Pad	Transformer Pad	41.00				0.668	13
		Sum	41.00		0.02			
13	Light Pole	Light Pole	302.00				0.851	13
		Sum	302.00		0.15			
					264.38	TONS		

